

NOTICE TO CONTRACTORS

CALL ORDER 400
 STATE PROJECT NO. PEP-30-5(1041)
 LOCATION: US-30, CLARKS-SILVER CREEK
 COUNTIES: MERRICK

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on October 04, 2007. At that time the bids will be opened and read for BITUMINOUS

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 13.9 MILES
 START DATE 07/14/2008 WORKING DAYS 60
 Price Range \$ 2,000,000 to \$ 4,000,000

Plans and specifications may be seen beginning September 11, 2007 at the Lincoln Central Office and September 17, 2007 at the District Engineer's Office at GRAND ISLAND
 Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

INFORMATIONAL PROPOSAL		EACH	\$	5.00
PLANS (NOT INCLUDING STANDARDS)	10	SHEETS	\$	2.50
STANDARD PLANS	4	SHEETS	\$	1.00

SHEET NO.

1	TITLE PAGE
2T1-2T6	TYPICAL CROSS SECTIONS
2S	SUMMARY OF QUANTITIES
2N	GENERAL INFORMATION--MILLED RUMBLE STRIPS
3	TEMPORARY PAVEMENT MARKING PLAN

STANDARD PLANS

920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R7	(2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 9 BITUMINOUS

BARRICADE, TYPE II	600	B	DAY
BARRICADE, TYPE III	444	B	DAY
TEMPORARY SIGN DAY	972	E	EACH
SIGN DAY	11,744	E	EACH
OVERLAY BROKEN LINES	2,167	S	STA
OVERLAY SOLID LINES	4,334	S	STA
FLAGGING	104	D	DAY
FURNISHING AND OPERATING PILOT VEHICLE	52	D	DAY
TRAFFIC CONTROL MANAGEMENT	111	D	DAY
FIELD OFFICE	1	E	EACH
MOBILIZATION	LUMP	L	LUMP
CONC PVMT REPAIR TYPE A FULL DEPTH	61	C	CY
CONC PVMT REPAIR TYPE B FULL DEPTH	265	C	CY
CONC PVMT REPAIR TYPE C FULL DEPTH	37	C	CY
HYDRATED LIME FOR ASPHALT MIXTURES	331	T	TON
HYD LIME FOR ASPH MIXES FOR ST MAIN PATC	5	T	TON
ASPH CONC FOR STATE MAINT PATCHING, TYPE SP4(0.5)	500	T	TON
ASPH CONCRETE FOR PATCHING, TYPE SP4(0.5)	300	T	TON
ASPH CONC, TYPE SPS	10,100	T	TON
ASPH CONC, TYPE SP4(0.5)	32,810	T	TON
PERF GRAD BIND (64-28)FOR ST MAINT PATCH	30	T	TON

GROUP 9 BITUMINOUS

PERF GRADED BINDER (58-28)	546 TON
PERF GRADED BINDER (64-28)	1,788 TON
PREP EXPANSION RELIEF JOINT	1,344 LF
TACK COAT	59,210 GAL
RENTAL OF LOADER, FULLY OPERATED	70 HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED	70 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	70 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	70 HOUR
WATER	325 MGAL
EARTH SHOULDER CONSTRUCTION	1,297 STA
COLD MILLING, CLASS 3	718 STA
COLD MILLING, CLASS 4	493 SY
COLD MILLING, CLASS 3	38 STA
TYPE A	
RUMBLE STRIPS, ASPHALT	1,454 STA
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP LUMP
SEEDING, TYPE B	20 ACRE
MULCH	45 TON