

STATE OF NEBRASKA  
DEPARTMENT OF ROADS  
ADDENDUM NO. 3  
PROJECT NO. IM-480-9(101)  
CONTROL NO. 22197  
CALL ORDER 200  
I-480, I-80 – DEWEY STREET, OMAHA  
LETTING DATE: NOVEMBER 8, 2007

The Special Provisions are amended to include the following:

**CONCRETE PAVEMENT REPAIR**

The following information concerning size and location of the Concrete Pavement Repair, Types A, B and C, areas are estimates by NDOR Materials & Research (M&R) personnel gathered from surveys taken from the shoulders of I-80 and I-480. The reason for this type of information gathering was due to the high volumes of traffic along these roadways. It is the NDOR's intent to have M&R personnel available on site to work with the Contractor to accurately mark the location of these repair areas under Contractor generated lane closures which are part of the project. The Project Manager will have M&R personnel attend the pre-construction conference so the M&R personnel and the Contractor can schedule their operations so as to determine the exact sizes and locations of all concrete repair areas.

Estimated Joint & Concrete Repair Areas

Repair Type	Location	Approximate No.	Approximate Quantity
Joint Repair	NB I-480	20 joints	53.2 cy
	SB I-480	16 joints	42.6 cy
	WB I-80	<u>40 joints</u>	<u>106.4 cy</u>
	TOTALS	76 repairs	202.2 cy
Conc. Repair Type A, F.D.	NB I-480	270 repairs	216.0 cy
	SB I-480	125 repairs	100.0 cy
	WB I-80	<u>200 repairs</u>	<u>160.0 cy</u>
	TOTALS	595 repairs	476.0 cy
Conc. Repair Type B, F.D.	NB I-480	8 repairs	21.0 cy
	SB I-480	5 repairs	18.0 cy
	SB I-80	<u>5 repairs</u>	<u>18.0 cy</u>
	TOTALS	18 repairs	57.0 cy

Conc. Repair			
Type C, F.D.	NB I-480	7 repairs	199.3 cy
	SB I-480	6 repairs	122.5 cy
	SB I-80	<u>4 repairs</u>	<u>41.7 cy</u>
	TOTALS	17 repairs	363.5 cy

DEPARTMENT OF ROADS



Claude Oie  
Construction Engineer

Issued: November 7, 2007

CO:AH:200AD311

NOTICE: Only the contractors issued bidding proposals receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the contractor.