

Metric AUP Summary For July 2006 thru June 2007

STANDARD		TOTAL		AVERAGE	TOTAL
ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS	UNIT PRICE	BID
0001.08	BARRICADE, TYPE II	38,155.00	BDAY	\$0.50	\$19,077.50
0001.10	BARRICADE, TYPE III	5,564.00	BDAY	\$1.47	\$8,170.28
0001.75	TEMPORARY SIGN DAY	900.00	EACH	\$4.82	\$4,338.00
0001.90	SIGN DAY	16,260.00	EACH	\$0.53	\$8,619.32
0001.99	CONTRACTOR FURNISHED SIGN DAY	1,868.00	EACH	\$0.40	\$741.68
0002.30	PAVEMENT MARKING REMOVAL	200.00	m	\$2.21	\$442.00
0002.44	TEMPORARY PAVEMENT MARKING, TYPE PAINT	800.00	m	\$2.21	\$1,768.00
0002.47	TEMPORARY PAVEMENT MARKING SURFACE PREPARATION	300.00	m	\$2.21	\$663.00
0002.55	OVERLAY BROKEN LINES	531.90	StaM	\$27.12	\$14,423.39
0002.60	OVERLAY SOLID LINES	1,063.80	StaM	\$25.62	\$27,254.92
0002.76	PERMANENT PAVEMENT MARKING PAINT	46,233.90	m	\$0.27	\$12,317.80
0003.10	FLAGGING	120.00	DAY	\$200.42	\$24,050.00
0003.70	TEMPORARY RUMBLE STRIP	4.00	EACH	\$442.80	\$1,771.20
0003.75	TEMPORARY TRAFFIC SIGNAL	1.00	EACH	\$13,989.00	\$13,989.00
0010.04	FIELD OFFICE	3.00	EACH	\$883.33	\$2,650.00
0030.00	MOBILIZATION	3.00	LS	\$1,255.83	\$3,767.50
0030.10	MOBILIZATION	3.00	LS	\$7,632.00	\$22,896.00
0030.40	MOBILIZATION	2.00	LS	\$7,000.00	\$14,000.00
0030.50	MOBILIZATION	1.00	LS	\$5,000.00	\$5,000.00
0030.60	MOBILIZATION	3.00	LS	\$28,000.00	\$84,000.00
0030.70	MOBILIZATION	2.00	LS	\$250.00	\$500.00
0030.90	MOBILIZATION	2.00	LS	\$42,500.00	\$85,000.00
1000.00	LARGE TREE REMOVAL	65.00	EACH	\$57.08	\$3,710.00
1009.00	GENERAL CLEARING AND GRUBBING	3.00	LS	\$3,600.00	\$10,800.00
1010.01	EXCAVATION (ESTABLISHED QUANTITY)	6,421.00	m3	\$3.99	\$25,607.13
1011.00	WATER	769.00	kL	\$2.90	\$2,230.10
1030.00	EARTHWORK MEASURED IN EMBANKMENT	7,627.00	m3	\$9.31	\$71,040.78
1043.50	RIPRAP FILTER FABRIC	2,814.00	m2	\$2.73	\$7,687.60
1102.00	REMOVE ASPHALT SURFACE	300.00	m2	\$11.89	\$3,567.00
1143.00	REMOVE DRIVEWAY CULVERT PIPE	6.00	m	\$20.00	\$120.00
1300.42	1050 mm DRIVEWAY CULVERT PIPE	23.00	m	\$158.41	\$3,643.43
1320.24	600 mm CORRUGATED METAL PIPE FOR DRIVEWAY CULVERT PIPE	12.50	m	\$92.54	\$1,156.75
2001.00	GRAVEL SURFACE COURSE	33.00	m3	\$46.87	\$1,546.71
2009.10	GRAVEL EMBEDMENT	1.31	StaM	\$2,907.00	\$3,805.26
2009.51	CRUSHED ROCK EMBEDMENT	5.86	StaM	\$421.43	\$2,470.00
2010.03	CRUSHED ROCK SURFACE COURSE	577.00	Mg	\$21.98	\$12,684.55
2020.00	SPECIAL SURFACE COURSE FOR MAILBOX TURNOUTS	507.00	m2	\$4.72	\$2,393.55

Metric AUP Summary For July 2006 thru June 2007

STANDARD		TOTAL		AVERAGE	TOTAL
ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS	UNIT PRICE	BID
2021.00	MAILBOX POST	21.00	EACH	\$58.81	\$1,235.00
4050.01	EXCAVATION FOR PIPE, PIPE-ARCH CULVERTS, AND HEADWALLS	878.00	m3	\$9.59	\$8,420.80
4051.01	EXCAVATION FOR BOX CULVERTS	275.00	m3	\$22.00	\$6,050.00
4054.68	TEMPORARY SHORING	45.00	LS(m2)	\$288.42	\$12,979.00
4095.20	COPING	63.00	m	\$145.74	\$9,181.62
4100.06	CLASS 47B-20 CONCRETE FOR HEADWALL	9.74	m3	\$605.00	\$5,892.70
4101.06	CLASS 47B-20 CONCRETE FOR BOX CULVERT	202.96	m3	\$654.08	\$132,752.08
4150.00	REINFORCING STEEL FOR HEADWALL	380.00	kg	\$2.65	\$1,007.00
4151.00	REINFORCING STEEL FOR BOX CULVERT	14,046.00	kg	\$1.97	\$27,670.62
4300.24	600 mm CULVERT PIPE	20.00	m	\$70.49	\$1,409.80
4300.48	1200 mm CULVERT PIPE	15.30	m	\$208.96	\$3,197.09
4310.24	600 mm FLARED-END SECTION	1.00	EACH	\$202.00	\$202.00
4310.48	1200 mm FLARED-END SECTION	2.00	EACH	\$740.00	\$1,480.00
4350.24	600 mm CORRUGATED METAL PIPE	38.10	m	\$102.00	\$3,886.20
4350.60	1500 mm CORRUGATED METAL PIPE	60.00	m	\$356.00	\$21,360.00
4360.24	600 mm METAL FLARED-END SECTION	6.00	EACH	\$353.33	\$2,120.00
6000.10	ABUTMENT NO.1 EXCAVATION	144.60	LS(m3)	\$69.16	\$10,000.00
6000.11	ABUTMENT NO.2 EXCAVATION	145.20	LS(m3)	\$68.87	\$10,000.00
6001.00	BENT NO.1 EXCAVATION	32.00	LS(m3)	\$218.75	\$7,000.00
6001.01	BENT NO.2 EXCAVATION	32.00	LS(m3)	\$218.75	\$7,000.00
6001.50	BENT NO.1 EXCAVATION	125.00	LS(m3)	\$124.00	\$15,500.00
6001.51	BENT NO.2 EXCAVATION	65.00	LS(m3)	\$238.46	\$15,500.00
6001.52	BENT NO.3 EXCAVATION	85.00	LS(m3)	\$76.47	\$6,500.00
6005.78	EXPANSION BEARING, TFE TYPE	12.00	EACH	\$800.00	\$9,600.00
6005.83	FIXED BEARING	4.00	EACH	\$800.00	\$3,200.00
6010.22	CLASS 47B-20 CONCRETE FOR BRIDGE	455.00	m3	\$441.38	\$200,827.50
6010.26	CLASS 47BD-30 CONCRETE FOR BRIDGE	484.20	m3	\$405.93	\$196,549.50
6020.00	REINFORCING STEEL FOR BRIDGE	34,925.00	kg	\$1.40	\$48,895.00
6040.00	REMOVE STRUCTURE	4.00	EACH	\$9,875.00	\$39,500.00
6071.12	STEEL SUPERSTRUCTURE	47,300.00	LS(kg)	\$2.96	\$140,000.00
6080.00	STRUCTURAL STEEL FOR SUBSTRUCTURE	5,040.00	kg	\$6.12	\$30,824.90
6086.00	STRUCTURAL STEEL	216.00	kg	\$3.07	\$663.12
6105.01	ROCK RIPRAP, TYPE A	500.00	Mg	\$42.00	\$21,000.00
6105.02	ROCK RIPRAP, TYPE B	2,267.00	Mg	\$34.11	\$77,325.12
6131.50	EPOXY COATED REINFORCING STEEL	42,435.00	kg	\$1.76	\$74,733.30
6200.00	CONCRETE PILING	1,189.00	m	\$100.51	\$119,511.40
6210.12	HP 250 mm X 62 kg STEEL PILING	709.00	m	\$103.35	\$73,275.15

Metric AUP Summary For July 2006 thru June 2007

STANDARD		TOTAL		AVERAGE	TOTAL
ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS	UNIT PRICE	BID
6310.00	STEEL SHEET PILING	921.30	m2	\$165.20	\$152,198.16
7017.00	REMOVE GUARDRAIL	23.20	m	\$10.00	\$232.00
7017.50	REMOVE & SALVAGE GUARDRAIL	76.00	m	\$13.58	\$1,032.08
7020.00	BRIDGE APPROACH SECTIONS	6.00	EACH	\$1,967.33	\$11,804.00
7021.47	MELT	6.00	EACH	\$1,527.00	\$9,162.00
8022.12	HYDRATED LIME FOR ASPHALT MIXTURES	242.00	Mg	\$265.97	\$64,364.00
8022.14	HYDRATED LIME FOR ASPHALT MIXTURES FOR STATE MAINT PATCHING	1.00	Mg	\$278.00	\$278.00
8091.00	GRANULAR BACKFILL	95.00	m3	\$32.00	\$3,040.00
9000.74	ASPHALTIC CONCRETE FOR STATE MAINTENANCE PATCHING, TYPE	100.00	Mg	\$23.30	\$2,330.00
9005.00	ASPHALTIC CONCRETE FOR PATCHING, TYPE	844.00	Mg	\$37.02	\$31,248.00
9005.50	ASPHALTIC CONCRETE, TYPE SP4 SPECIAL(9.5)	13,450.00	Mg	\$23.30	\$313,385.00
9005.51	ASPHALTIC CONCRETE, TYPE SP4 SPECIAL(12.5)	10,360.00	Mg	\$29.50	\$305,620.00
9009.00	PLACEMENT OF ASPHALTIC CONCRETE FOR DRIVEWAYS AND INTER	4,992.00	m2	\$2.80	\$13,995.10
9009.87	SURFACING 200mm	432.00	m2	\$63.00	\$27,216.00
9020.94	PERFORMANCE GRADED BINDER (64-28) FOR STATE MAINT PATCHING	6.40	Mg	\$457.00	\$2,924.80
9021.08	PERFORMANCE GRADED BINDER (64-28)	1,468.82	Mg	\$486.26	\$714,232.48
9034.00	PREPARATION OF INTERSECTIONS AND DRIVEWAYS	2,576.00	m2	\$2.22	\$5,706.75
9053.00	TACK COAT	112,880.00	L	\$0.37	\$41,284.50
9110.01	RENTAL OF LOADER, FULLY OPERATED	67.00	HOURL	\$60.15	\$4,030.00
9110.02	RENTAL OF MOTOR GRADER, FULLY OPERATED	40.00	HOURL	\$61.50	\$2,460.00
9110.03	RENTAL OF DUMP TRUCK, FULLY OPERATED	67.00	HOURL	\$49.03	\$3,285.00
9110.07	RENTAL OF SKID LOADER, FULLY OPERATED	67.00	HOURL	\$45.22	\$3,030.00
9110.27	RENTAL OF CRAWLER MOUNTED HYDRAULIC EXCAVATOR, FULLY OPERATED	27.00	HOURL	\$82.41	\$2,225.00
9111.00	WATER	1,046.00	kL	\$8.09	\$8,462.00
9170.00	EARTH SHOULDER CONSTRUCTION	349.94	StaM	\$106.71	\$37,342.32
9173.20	SUBGRADE PREPARATION	432.00	m2	\$3.45	\$1,490.40
9179.23	COLD MILLING, CLASS 3	98.48	StaM	\$440.00	\$43,329.00
9179.33	COLD MILLING, CLASS 3	54,358.00	m2	\$0.55	\$29,896.90
L001.01	SEEDING, TYPE A	3.50	ha	\$1,768.00	\$6,188.00
L001.02	SEEDING, TYPE B	5.40	ha	\$2,160.00	\$11,664.00
L006.00	COVER CROP SEEDING	5.40	ha	\$408.70	\$2,207.00
L006.50	TEMPORARY SEEDING	0.07	ha	\$22,140.00	\$1,571.94
L020.03	EROSION CONTROL, TYPE C	1,843.00	m2	\$3.87	\$7,132.41
L020.10	EROSION CONTROL, TYPE HV	381.00	m2	\$1.49	\$567.69
L022.11	FABRIC SILT FENCE-LOW POROSITY	495.00	m	\$13.76	\$6,809.71
L022.12	FABRIC SILT FENCE-HIGH POROSITY	148.00	m	\$8.00	\$1,184.00
L022.90	TEMPORARY SILT FENCE	550.00	m	\$8.36	\$4,600.00

Metric AUP Summary For July 2006 thru June 2007

STANDARD		TOTAL		AVERAGE	TOTAL
ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS	UNIT PRICE	BID
L032.75	MULCH	44.00	Mg	\$112.70	\$4,959.00
L435.01	CEPHALANTHUS OCCIDENTALIS (BUTTONBUSH) 225mm-300mm B.R.	231.00	EACH	\$5.50	\$1,270.50
L441.23	CORNUS SERICEA (REDOSIER DOGWOOD) 225mm-300mm B.R.	69.00	EACH	\$9.75	\$672.75
L549.88	PRUNUS AMERICANA (AMERICAN WILD PLUM) 500mm-600mm B.R.	124.00	EACH	\$3.90	\$483.60
L562.35	RIBES MISSOURIENSE (GOOSEBERRY) 300mm-400mm B.R.	59.00	EACH	\$43.00	\$2,537.00
L569.99	SHEPERDIA ARGENTEA (SILVER BUFFALO BERRY) 400mm-500mm B.R.	51.00	EACH	\$11.75	\$599.25
L600.98	SYMPHORICARPOS ORBICULATUS 'ALBA' (SNOWBERRY) 300mm-400mm B.R.	271.00	EACH	\$3.60	\$975.60
L600.99	SYMPHORICARPOS ORBICULATUS (INDIAN CURRANT CORALBERRY) 300mm-400mm B.R.	147.00	EACH	\$7.20	\$1,058.40
L705.21	ACER SACCHARINUM (SILVER QUEEN MAPLE) 1.8 m - 2.0 m BRANCHED B.R.	4.00	EACH	\$67.50	\$270.00
L707.95	AMELANCHIER X GRANDIFLORA 'AUTUMN BRILLIANCE' (AUTUMN BRILLIANCE SERVICEBERRY) 1.8 m -2.0 m BRANCHED B.R.	93.00	EACH	\$60.00	\$5,580.00
L717.13	CELTIS OCCIDENTALIS (COMMON HACKBERRY) 2.0 m - 2.5 m B&B OR CONTAINER GROWN	28.00	EACH	\$88.50	\$2,478.00
L750.23	FRAXINUS AMERICANA 'AUTUMN PURPLE' (AUTUMN PURPLE ASH) 2.0 m - 2.5 m BRANCHED B.R.	51.00	EACH	\$105.00	\$5,355.00
L750.46	FRAXINUS PENNSYLVANICA 'CIMMERON' (CIMMERON ASH) 2.0 m - 2.5 m BRANCHED B.R.	102.00	EACH	\$77.50	\$7,905.00
L755.08	FRAXINUS PENNSYLVANICA 'PATMORE' (PATMORE ASH) 2.0 m - 2.5 m BRANCHED B.R.	150.00	EACH	\$75.00	\$11,250.00
L774.05	MALUS "PRAIRIFIRE" (PRAIRIFIRE CRABAPPLE) 1.8 m - 2.0 m BRANCHED B.R.	89.00	EACH	\$64.00	\$5,696.00
L774.18	MALUS 'INDIAN SUMMER' (INDIAN SUMMER CRABAPPLE) 1.8 m - 2.0 m BRANCHED B.R.	62.00	EACH	\$60.50	\$3,751.00
L787.81	PLATANUS AMERICANA (AMERICAN PLANE TREE) 2.0 m - 2.5 m BRANCHED B.R.	13.00	EACH	\$300.00	\$3,900.00
L793.16	POPULUS DELTOIDES 'MIGHTY MOE' (MIGHTY MOE COTTONWOOD) 2.0 m - 2.5 m BRANCHED B.R.	65.00	EACH	\$50.50	\$3,282.50
L800.71	PRUNUS SEROTINA (COMMON BLACK CHERRY) 1.8 m - 2.0 m BRANCHED B.R.	16.00	EACH	\$194.40	\$3,110.40
L807.21	QUERCUS BICOLOR (SWAMP WHITE OAK) 2.0 m - 2.5 m B&B OR C.G.	19.00	EACH	\$101.50	\$1,928.50
L808.05	QUERCUS RUBRA (NORTHERN RED OAK) 2.0 m - 2.5 m B&B OR C.G.	5.00	EACH	\$115.00	\$575.00
L825.51	SALIX INTERIOR (SANDBAR WILLOW) 1.8 m - 2.0 m BRANCHED B.R.	141.00	EACH	\$43.00	\$6,063.00
L835.17	TILIA AMERICANA (AMERICAN LINDEN) 2.0 m - 2.5 m B&B OR C.G.	15.00	EACH	\$82.00	\$1,230.00