



FAIRVIEW ROAD INTERCHANGE

PROJECT NO. NH-75-2(165), C.N. 21849C

LOCATION: The improvements will begin approximately ¾ mile south of the Fairview Road intersection with US-75 and proceed north for approximately 1 ¼ miles on US-75.

INTENT OF PROJECT: The intent of the improvements to the Fairview Road Interchange is to provide a safer interchange that will carry future traffic volumes efficiently and safely.

SCOPE OF WORK: The existing interchange at Fairview Road will be reconstructed to a more typical diamond interchange. The existing southbound off-ramp will be used-in-place. A new southbound on-ramp will be constructed and will replace the existing flyover. New northbound on and off-ramps will also be constructed. Fairview Road will be reconstructed approximately 3000' east of the interchange. Fairview Road will also be reconstructed approximately 2000' west of the interchange by others. Fort Crook Road will be shifted to the east to provide for a greater separation from the ramp terminals and will tie-in to its existing location south of the bridge over the Papio Creek. A new frontage road will provide access along the east side of US-75 to Grenoble Drive.

TRAFFIC COUNT:

Year	2005 Average	2030 Average
	Daily Traffic	Daily Traffic
Fairview Road (West of US-75)	4,000	14,800
Fairview Road (East of US-75)	500	8,000

BRIDGE: No new bridges will be constructed on the project.

ESTIMATED CONSTRUCTION SCHEDULE: (Subject to the availability of funds). This 1 ¼ mile project is currently scheduled to be constructed no earlier than 2009.

ACCOMMODATION OF TRAFFIC: Traffic will be maintained during construction. Temporary roads will be constructed to accommodate traffic.

RIGHT-OF-WAY NEEDS: Right-of-way and temporary construction easements will be required.

WETLANDS: Wetlands will be impacted with mitigation to be established within the project corridor.

ESTIMATED PROJECT COST: The estimated cost for this project is \$8,700,000 dollars.