

## **SECTION 308 -- MEDIAN CONSTRUCTION**

### **308.01 -- Description**

Median construction shall consist of placing embankment on non-surfaced medians to the elevations shown in the plans.

### **308.02 -- Material Requirements**

1. Embankment materials shall be obtained from the locations shown in the plans.

2. Soil required for embankments shall meet the requirements of Subsection 205.02.

### **308.03 -- Construction Methods**

1. The Contractor shall construct medians as indicated in the plans.

2. The work shall be performed in accordance with the requirements of Subsection 304.03.

### **308.04 -- Method of Measurement**

Median Construction shall be measured in stations of 100 feet, regardless of width or thickness. Stations shall be measured horizontally along the project centerline between the beginning and ending points.

### **308.05 -- Basis of Payment**

<b>1. Pay Item</b>	<b>Pay Unit</b>
Median Construction	Station (Sta)
Water	1,000 Gallons (MGAL)

2. Payment is full compensation for all work prescribed in this Section.