## 807.00 EROSION CONTROL

## 807.01 EROSION CONTROL CHECKLIST

SSHC Reference: Section 807 -- Erosion Control & Special Provisions

Other References: Approved Products List

Inspection Crew: Construction Technician

Inspection Equipment: NA

General Comments:

1. Has the finish grade been accepted for this area? (SSHC Subsection 807.03, Para. 1)

- 2. Is the material on the approved products list? (SSHC Subsection 807.02, Para. 1)
- 3. Does the contractor have the right pins? (SSHC Subsection 807.02, Para. 2)
- 4. Does the contractor have the right fertilizer? (Special Provisions)
- 5. Is the seed bed properly prepared? (SSHC Subsection 807.03, Para. 4)
- 6. Does the seed have the department tags for this project? (SSHC Subsection 803.02, Paragraphs 3 & 4)
- 7. Usual work sequence:
  - a. Soil preparation including the slots for the erosion checks
  - b. Fertilize
  - c. Install filter fabric for check slots and soil fill
  - d. Seed and rake the seed into the soil
  - e. Install erosion control material
  - f. Some erosion control materials come with the filter fabric attached. When this material is used, direct seed into the erosion control material and then soil is spread over the seed
- 8. Questions -- call 402-479-4537, Roadside Development.

## 807.02 FILTER FABRIC

@

Cut the fabric so that the excess material lies under the outlet so that the water falls on a double layer. this is shown on the plans.

The filter fabric detail should show the fabric covering the area above a box culvert opening and the boxes wings.

The bale check includes the necessary filter fabric so do not include this quantity when calculating the pay quantity for filter fabric. Pay limits will be added to the plan detail.

