

SECTION 206 -- ROADWAY GRADING

206.01 -- Description

"Roadway Grading" shall consist of furnishing, excavating, loading, hauling, placing, compacting, and finishing all materials necessary for the completion of the roadway, including its embankments, intersections, driveways, and approaches as shown in the plans.

206.02 -- Material Requirements

Soils that are placed in embankments and required in the roadway grading pay item shall meet the requirements of Subsection 205.02.

206.03 -- Construction Methods

1. The Contractor shall construct the roadway as shown in the plans.
2. The Contractor shall maintain all areas during the construction operations so that they will be adequately drained at all times.
3. The Contractor shall remove all excess material.
4. The Contractor shall obtain borrow material as indicated in the plans.
5. The Contractor shall perform the excavation, placement, sloping, and finishing of soils as prescribed in Section 205. The embankment shall be compacted to comply with the compaction requirements shown in the plans.
6. The Contractor shall obliterate roads and shape the constructed areas to blend naturally with the surrounding areas.

206.04 -- Method of Measurement

1. "Roadway Grading" will be measured for payment by stations of 100 feet, measured horizontally along the centerline of the project.
2. Deductions will be made for bridge floors 20 feet or more in length.
3. Sections having roadway grading on only one side of the road shall be measured along the centerline of the project, and then the measured distance shall be divided by 2 to obtain the pay quantity.
4. No additional allowance will be made for the work required to complete intersection and driveway returns, tapers, curves, tangents, stubs, and other irregular areas.

206.05 -- Basis of Payment

1.	<u>Pay Item</u>	<u>Pay Unit</u>
	Roadway Grading	Station (Sta)

2. When borrow and waste sites are obtained by the Department and shown in the plans and the Contractor elects to use other sites, the Contractor shall be charged with all costs that are incidental to obtaining the sites shown in the plans. These charges shall be deducted from Department monies due the Contractor.

3. Clearing and grubbing of borrow and waste sites shown in the plans shall be measured and paid for in accordance with Subsections 202.03 and 202.04. When borrow is obtained from sites which are not shown in the plans, no payment will be made for clearing and grubbing.

4. Water applied shall be subsidiary to "Roadway Grading."

5. Payment is full compensation for all work prescribed in this Section.