

## SECTION 308 -- MEDIAN CONSTRUCTION

### 308.01 -- Description

Median construction shall consist of placing embankment on non-surfaced medians to the elevations shown in the plans.

### 308.02 -- Material Requirements

1. Embankment materials shall be obtained from the locations shown in the plans.
2. Soil required for embankments shall meet the requirements of Subsection 205.02.

### 308.03 -- Construction Methods

1. The Contractor shall construct medians as indicated in the plans.
2. The work shall be performed in accordance with the requirements of Subsection 304.03.

### 308.04 -- Method of Measurement

Median Construction shall be measured in stations of 100 feet, regardless of width or thickness. Stations shall be measured horizontally along the project centerline between the beginning and ending points.

### 308.05 -- Basis of Payment

- | 1. | <u>Pay Item</u>     | <u>Pay Unit</u>      |
|----|---------------------|----------------------|
|    | Median Construction | Station (Sta)        |
|    | Water               | 1,000 Gallons (MGAL) |
2. Payment is full compensation for all work prescribed in this Section.