

SECTION 406 -- PULL BOXES

406.01 -- Description

1. The Contractor shall construct pull boxes of the size, type, and at the locations shown in the plans and, if required, install a spare bend in the pull box as shown in the plans. This work shall include furnishing and installing the pull box, spare conduit bend, grounding connectors and ground rod (if required), washed rock, and all excavation, backfilling, compaction, labor, equipment, tools, and incidentals required to complete the work.

2. The Contractor shall relocate pull boxes as shown in the plans. A spare bend, if required, shall be installed in the relocated pull box as shown in the plans. "Relocate Pull Box, Type PB _____" shall include removing the existing pull box, installing the pull box at the new location, tapping into existing conduit, extending conduit to the relocated pull box, spare conduit bend(s), grounding connectors and ground rod(s) (if required), washed rock, and all excavation, backfilling, compaction, labor, equipment, tools, and incidentals required to complete the work.

406.02 -- Material Requirements

1. Pull boxes shall conform to the requirements shown in the plans.
2. Pull boxes shall be on the NDR Approved Products List.

406.03 -- Construction Methods

1. Pull boxes shall not be constructed in ditch bottoms, low areas where ponding of water may occur, or where they will be subjected to vehicular traffic.
2. Pull boxes shall not have concrete bottoms.

406.04 -- Method of Measurement

Pull boxes and relocated pull boxes shall be measured by the each.

406.05 -- Basis of Payment

- | 1. | <u>Pay Item</u> | <u>Pay Unit</u> |
|----|----------------------------------|-----------------|
| | Pull Box, Type PB _____ | Each (ea) |
| | Relocate Pull Box, Type PB _____ | Each (ea) |
2. Payment is full compensation for all work prescribed in this Section.