

SECTION 904 -- INERTIAL BARRIER MODULES

904.01 -- Description

The Contractor shall furnish and install sand filled inertial barrier modules (impact attenuators) at the locations shown in the plans.

904.02 -- Material Requirements

1. The inertial barrier modules shall be listed on the NDR Approved Materials List.
2. Filler material for inertial barrier modules shall meet the material and gradation requirements shown in the plans.

904.03 -- Construction Methods

The Contractor shall install the inertial barrier modules in accordance with the recommendations and instructions of the manufacturer and as directed by the Engineer.

904.04 -- Method of Measurement

1. The inertial barrier modules shall be measured by the each.
2. Filler material shall be measured by the cubic yard.

904.05 -- Basis of Payment

- | <u>Pay Item</u> | <u>Pay Unit</u> |
|--|-----------------|
| Inertial Barrier Modules, Type _____ | Each (ea) |
| Filler Material for Inertial Barrier Modules | Cubic Yard (CY) |
2. Payment is full compensation for all work prescribed in this Section.