

SECTION 421 -- REMOVING AND RESETTING DELINEATORS

421.01 -- Description

The Contractor shall remove and reset flexible post and standard delineators at the locations shown in the plans.

421.02 -- Construction Methods

1. The Contractor shall remove the delineators, intact, and stockpile them at designated locations for future resetting.
2. Any material lost or damaged shall be replaced by the Contractor at no additional cost to the Department.
3. The delineators shall be set plumb and anchored as prescribed in the plans.

421.03 -- Method of Measurement

Removing and resetting delineators will be measured by the each.

421.04 -- Basis of Payment

- | | | |
|----|---|-----------------|
| 1. | <u>Pay Item</u> | <u>Pay Unit</u> |
| | Remove & Reset Delineators | Each (ea) |
| | Remove & Reset Flexible Post
Delineators | Each (ea) |
2. Payment is full compensation for all work prescribed in this Section.