

SECTION 726 -- CULVERT SANDFILL

726.01 -- Description

This work shall consist of sealing existing culverts as shown in the plans or as directed by the Engineer. The Contractor shall construct bulkheads at the outlet ends and then filling the culvert with sand or flowable fill.

726.02 -- Material Requirements

1. Flowable fill shall meet the requirements of Section 1003.
2. Concrete shall meet the requirements of Section 1002.
3. Sand shall meet the requirements of Subsection 1033.02, Paragraph 3.a.

726.03 -- Construction Methods

1.
 - a. The Contractor shall plug the culverts at locations shown in the plans.
 - b. The plug shall be a bulkhead or other structure as shown in the plans.
2. The Contractor shall fill the culvert with flowable fill, sand, or fine aggregate for concrete.

726.04 -- Method of Measurement

Culvert sandfill is measured by the cubic meter. The plan quantities shall be based on the lengths and diameters of the pipes shown in the plans.

726.05 -- Basis of Payment

- | | | |
|----|---|-------------------------------|
| 1. | <u>Pay Item</u> | <u>Pay Unit</u> |
| | Culvert Sandfill | Cubic Meter (m ³) |
| 2. | Payment is full compensation for all work prescribed in this Section. | |