

SECTION 913 -- RIGHT-OF-WAY MARKERS

913.01 -- Description

The Contractor shall furnish, install, and relocate right-of-way markers as prescribed in the plans.

913.02 -- Material Requirements

1. Concrete shall be Class 47BD-20.
2. Reinforcing steel shall meet the requirements of Section 1020.
3. One or more markers shall be broken to facilitate a visual inspection of the quality and dimensions of the concrete and reinforcing steel.

913.03 -- Construction Methods

1. The Contractor shall install and/or relocate the right-of-way markers as indicated in the plans.
2. The forms shall be designed so the finished marker will conform to the dimensions shown in the plans.
3. Reinforcement shall be placed and wired in position so that the reinforcing steel will not be displaced during concrete placement and consolidation.
4. The concrete shall be thoroughly consolidated by hand methods or mechanical vibration.
5. All surfaces shall be given an "Ordinary Surface Finish" in accordance with Subsection 704.03.
6. All markers cracked or broken in handling or delivery shall be rejected.
7. Markers removed during construction operations shall be stored near the site of removal and protected from all damage until they have been reset.
8. Excavation shall be made to the required depth and the markers set plumb and firm. The marker holes shall be at least 100 mm larger than each dimension of the marker's base. The area shall be backfilled with suitable material compacted with mechanical or hand tampers.

913.04 -- Method of Measurement

1. The quantity of "Right-of-Way Markers" is measured by the each.
2. The quantity of right-of-way markers that are reset is measured by the each.

913.05 -- Basis of Payment

- | 1. | <u>Pay Item</u> | <u>Pay Unit</u> |
|----|----------------------------|-----------------|
| | Right-of-Way Markers | Each (ea) |
| | Reset Right-of-Way Markers | Each (ea) |
2. Removal of damaged markers shall be subsidiary to the marker pay item.
 3. Payment is full compensation for all work prescribed in this Section.